



केन्द्रीय विद्यालय खगड़िया  
KENDRIYA VIDYALAYA KHAGARIA

श्यामलाल नगर , जिला :- खगड़िया (बिहार) पिन -851205  
Shyam Lal Nagar, Distt.:- Khagaria(Bihar) , PIN : 851205  
फैक्स न०:- 06244-226482 , फोन न०:- 06244-223407  
Fax no.-06244-226482 , Phone No:- 06244-223407  
Web site: www.kvkhagaria.ac.in , E-mail:- kv.khagaria@yahoo.com

एफ.क्र.38 /के.वि.खग./2019-20

दिनांक: 05/09/2019

सेवा में,

विज्ञापन प्रबंधक

प्रभात खबर, भागलपुर

विषय :- विज्ञापन (टेंडर सूचना) प्रकाशित करने के संबंध में ।

महाशय,

निवेदन पूर्वक कहना यह है कि आपके समाचार पत्र प्रभात खबर (खगड़िया)

एडिशन में दिनांक 06.09.2019 को निम्नलिखित टेंडर सूचना प्रकाशित करना चाहता हूँ ।

**टेंडर सूचना**

केन्द्रीय विद्यालय खगड़िया (बिहार) में विद्यालय के मरम्मत कार्य , टाईल्स, कोटा स्टोन, ढलाई, प्लास्टर , ब्रिक कार्य, पाईलिंग एवं रंगाई पुताई हेतु दर रजिस्टर फार्म संख्या, जी.एस.टी.न०., पैन न० धारको से सीलबंद लिफाफा में निविदा इस कार्यालय को दिनांक 26.09.2019 (5:00 बजे शाम तक) सिर्फ स्पीड पोस्ट अथवा पंजीकृत डाक से पहुंच जाना चाहिए । निविदा कार्य दस्तावेज़ केन्द्रीय विद्यालय खगड़िया की बेबसाईड <http://www.khagaria.kvs.ac.in> से डाउनलोड करें । निविदाएँ 27.09.2019 को दोपहर 3:00 बजे निविदा व्यक्ति एवं विद्यालय क्रेता सदस्य के संमक्ष खोली जाएगी ।

प्राचार्य

यह आपके सूचना प्रेषित एवं आवश्यक कार्यवाई हेतु ।

सधन्यवाद

भवदीय

राजेश कुमार  
(राजेश कुमार) 5/9/19

प्राचार्य/Principal  
केन्द्रीय विद्यालय, खगड़िया  
Kendriya Vidyalaya, Khagaria



केन्द्रीय विद्यालय खगड़िया  
KENDRIYA VIDYALAYA KHAGARIA

श्यामलाल नगर , जिला :- खगड़िया (बिहार) पिन -851205  
Shyam Lal Nagar, Distt.:- Khagaria(Bihar) , PIN : 851205  
फैक्स नं:- 06244-226482 , फोन नं:- 06244-223407  
Fax no. 06244-226482 , Phone No:- 06244-223407  
web site: www.kvkhagaria.ac.in , E-mail:- kv.khagaria@yahoo.com


एफ.क.38 /के.वि.खग./2019-20

दिनांक: 04/09/2019

Sl.No	DESCRIPTION OF WORK	QTY	PRICE
1	Supply & Fixing Iron gates, top hung, consisting of channel pickets pickets, pivoted flat bars top and bottom runners brass handles etc. as specified, erected in position and securing runners with holdfasts and brackets complete.	SQM	
2	Supply and fixing framed work as in doors or gates of angle or other section with gusset plate complete doors etc to be prepared to hanging r sliding with and including either books and hinges or hanging door fittings and hanging also fastening and fixing article conforming to Fe 290 Gde E-165 complete.	KG	
3	Boring holes 300 mm dia of piles and 3m deep in soil for single under reamed piles and getting out and disposal of spoil to distance of app. 50m complete.	each	
4	All as per item here in above but 6 to 8 mm dia and over as in stirrups, spacer and birders complete.	KG	
5	Material and labour of providing reinforced cement concrete(1:2:4) type B1 (using 20mm graded stone aggregate) in foundations, including rafts, footing, foundations beams, plinth beams, reinforced cement concrete band base for columns, basement slabs, pedestal under reamed piles and mass concrete etc. including necessary use and waste of form work complet all as specified and directed.	CUB	
6	Material & labour mild steel TMT bars 8 to 12 mm dia and over cut length bent to shape required including cranking bending spirally for hooping for columns hooking ends and binding with and including mild steel wire (annealed) not less than 0.9 mm dia or securing with clips.	KG	
7	Material & labour for 15-17mm thick prepolished granite stone slab, machine cut to size as in slab etc., set and joined in neat cement slurry and pointed in white or coloured cement to match the shade of the slab over and including 15 mm thick creed bed in cement mortar (1:4) and rounding off the exposed edges of granite including demolition of existing stone slab complete all as specified and erected.	SQM	
8	Roughening surface of Id concrete flor by pcking sweeping, cleaning and washing down with water to remove dust etc. complete.	SQM	
9	Material & labour for applying two coats of apex weather coat paint over and including preparation of old or new surfaces of wall, border, projection using two coats of Birla/JK Putty@2 kg/ sqm, including complete removal of existing wall furnish of any type with write brush, brooming, brooming, dusting and finally washing with water to clean the surface absolutely free from any kind of foreign materials and making good minor cracks etc.	SQM	
10	Material & labour for applying two coats of emulsion coat paint over and including preparation of old or new surfaces of wall, border, projection using two coats of Birla/JK Putty@2 kg/ sqm, including complete removal of existing wall for internal panting, furnish of any type with write brush, brooming, brooming, dusting and finally washing with water to clean the surface absolutely free from any kind of foreign materials and making good minor cracks etc.	SQM	



11	Material & labour for machine pressed made cement concrete interlocking paver block thickness not less than 80 mm any section manufacture using ordinary Portland cement with grey cement and no pigment using M-40 grade design mix concrete conforming to IS 15658-2006, laid over and including 50 mm thick layer of sand. The side of paver block shall be grouted with cement concrete (1:2:4) type B-0 (using 12.5 mm graded Stone.	SQM	
12	Demolition of cement concrete (unreinforced) in ground floors and paving n.exc 15 cm thickness (below or above ground level) and removal of the debris from site as directed	CUM	
13	Excavation in trenches n.exc. 1.5 m wide and n.exc 1.5 m in depth for foundation etc. or for shafts, wells, cesspits etc, n.exc 10 sqm on plan and n.exc 1.5 m in depth and getting out in soft/ loose soil etc. complete.	CUM	
14	Material & labour for sand filling under floors or in foundation including watering and consolidation complete.	CUM	
15	Material & labour brick work with sub class 'B' bricks straight or curved on plan exceeding 6 m mean radius, built in cement mortar(1:4) complete	CUM	
16	Material & labour for rendering 15 mm thick in cement mortar (1:4) on fair faces of brick work or concrete surface, finished even and smooth without using extra cement complete all as directed.	SQM	
17	Material & labour for providing 25 mm thick in cement concrete (1:2:4) type B-0 (using 12.5 mm graded stone aggregate) as in levelling course and PCC padding on roof to maintain proper slope, finished the surfaces even and fair complete all as specified and directed.	SQM	
18	Material & labour for providing 150 mm thick cement concrete (1:2:4) TYPE b-2 (using 40 mm graded stone aggregate) as in hard standing, paving etc. finished the cement concrete surfaces even and smooth and making impression of expanded metal, whilst the concrete is green complete all as specified and directed.	SQM	
19	Material & labour mild steel tubular pipe 100 mm bore heavy duty cut to Size fixed in floor with nuts and bolts as in posts complete all as specified and directed.	RM	
20	Supply and fixing mild steel tubular pipe 50 mm bore medium cut to length and fixed to walls for tubular roof trusses (frame) trussed, purlain, suspended false ceiling including two coats of synthetic enamel paint over a coat of red oxide primer complete.	RM	
21	Supply and fixing 20-40 mm bore tubes, medium grade, galvanized with all fittings and fixed complete on walls and ceiling or laid in floors etc. complete all as directed.	RM	
22	Supply and fixing 4 mm thick fiber glass reinforced translucent coloured corrugation side lap fixed with type or type or cranked hook bolts in roof, walls etc. complete.	SQM	
23	Supply and fixing for 4 mm plain colour PVC sheet reinforced etc complete all as specified and as per drawing.	RM	
24	Supply and fixing framed work as in doors or gates of angle or other section with gusset plates complete doors etc to be prepared to hanging or sliding with and including either hooks and hinges or hanging door fittings and hanging also fastening and fixing articles conforming to Fe 290 Gde E-165 complete.	KG	
25	Material & labour machine cut kota stone slab flooring 20-25 mm thick laid over and including 15 mm thick screed bed in cement mortar (1:4) and joined with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing with bees wax polishing complete.	SQM	

  
 प्राचार्य / Principal  
 केन्द्रीय विद्यालय, खगड़िया  
 Kendriya Vidyalaya, Khagaria

## List of Enclosure

1. Certificate of GST No.
2. Zerox copy of PAN No.
3. Registration of firm
4. ITR for lastest 3 years
5. Rate list of description of work
6. Address for sending tender

To,

The Principal  
Kendriya Vidyalay Khagaria  
Shyam Lal Nagar  
Dist. – Khagaria (Bihar)  
Pin No. 851205

*Signature*  
09/11/19  
Principal  
केंद्रीय विद्यालय, खगड़िया  
Kendriya Vidyalaya, Khagaria